IRRIGATION DIVISION.

Dated 20th November 1918.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Irrigation Division, up to 20th December 1918, for improving the channels of Iyenkere Tank, Kadur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1922.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees two hundred in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for improving the channels of Iyenkere Tank, Kadur Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Improving the channels of Iyenkere Tank, Kadur Taluk.

No.	Items of work	Per	Quantity	Rate Rs.	a.	p.	Cost Rs.
	BASAVANKALVE.						
	Head Works.						
1	Excavation in soft rock for foundation	C. yd.	85				
2	Surki concrete	C. ft.	67				
3	Burnt brick in surki mortar	"	48				
4	Cement concrete grouting	L. S.					
5	Surki plastering	Sq.	2·00				
6	New stone work	C. yd.	7				
7	Old stone work	"	18				
8	Repairing pin shutters with new planks whichever necessary including locking arrangements.	L. S.					
9	Concrete grouting including pointing	Sq.	1·32				
10	New burnt stone slabs	S. ft.	43				
	Channel Works.						
1	New furlong stones including cutting figures, painting and fixing ...	No.	3				
2	New bank grade stones at every half furlong including cutting figures, painting and fixing.	"	32				
3	New index stones including cutting figures, painting and fixing ...	"	32				
4	Cutting figures to existing furlong stones including painting and fixing	"	18				
5	Cutting figures to existing index stones including painting and fixing	"	30				
6	Painting to existing zero and mile stones	"	5				
7	New bed grade stones including dressing and fixing	"	40				
8	Removing and refixing existing bed grade stones	"	25				
9	Sluice number stones cutting figures and painting and fixing ...	"	15				
	Cart Bridges.						
1	Earthwork over roadway	C. yd.	59				
2	Surki plastering	Sq.	1·99				
3	Concrete grouting including pointing	"	1·55				
4	Dry stone wall work	C. ft.	112				
5	Removing and refixing the old slabs	S. ft.	7				
6	New burnt stone slabs	"	9				
	Relieving Weirs.						
1	New rough stone work	C. yd.	6				
2	New burnt stone slabs	S. ft.	18				
	Repairing and reconstructing Sluices.						
1	Earthwork, cut opening the bund, excavating foundations and refilling	L. S.					
2	Surki concrete	C. ft.	363				
3	Burnt brick in surki mortar	"	5,267				
4	Surki plastering	Sq.	54·2				
5	New rough stone work	C. yd.	184				
6	New burnt stone slabs	S. ft.	1,881				
7	Cutting two orifices in slabs	No.	22				
8	Cutting holes in guide slabs	"	22				
9	Sluice number stones	"	11				
10	Wooden plug with iron rod, leather washer locking arrangement, etc., complete.	"	15				
11	Repairs to sluices	L. S.					

No.	Items of work	Per	Quantity	Rate	Cost
				Rs. a. p	Rs.
	KADEKALVE.				
	Anicut Works.				
1	Earthwork gravel and stony soil and using to bund	C. yd.	120		
2	New stone work	„	138		
3	Old stone work	„	60		
4	Removing and refixing old slabs	S. ft.	200		
5	Surki plastering	Sq.	3·00		
6	Repairing the body wall returns and raising, etc.	L. S.			
	Head Works.				
1	Earthwork gravel and stony soil and using to bund	C. yd.	16		
2	Repairing pin shutters with new planks whatever necessary including locking arrangements.	L. S.			
	Channel Works.				
1	Earthwork gravel and stony soil and using to bund	C. yd,	13,406		
2	New furlong stones including cutting figures, painting and fixing ..	No.	2		
3	New bank grade stones at every half furlong including cutting figures, painting and fixing.	„	26		
4	New index stones including cutting figures, painting and fixing ...	„	30		
5	Cutting figures to existing furlong stones including painting and fixing.	„	22		
6	Painting to existing zero and mile stones	„	4		
7	Cutting figures to existing index stones, painting and fixing ...	„	22		
8	New bed grade stones including dressing and fixing	„	24		
9	Removing and refixing the available bed grade stones	„	27		
	Cart Bridges.				
1	Earthwork gravel and stony soil and using to bund	C. yd.	124		
2	New stone work	„	31		
3	Old stone work	„	6		
4	Removing and refixing old slabs	S. ft.	93		
5	Burnt brick in surki mortar	C. ft.	31		
6	Surki plastering	Sq.	2·10		
7	Concrete grouting including pointing	„	3·30		
8	New dry stone wall work	C. ft.	156		
9	New burnt stone slabs	S. ft.	26		
10	New guard stones	No.	4		
	Relieving Weirs.				
1	Earthwork using to bund	C. yd.	50		
2	New stone work	„	86		
3	Old stone work	„	16		
4	Burnt brick in surki mortar	C. ft.	38		
5	Surki plastering	Sq.	3·00		
6	New burnt stone slabs	S. ft.	49		
	Improving and reconstructing Sluices.				
1	Earthwork and using to bund	C. yd.	40		
2	New stone work	„	266		
3	Burnt brick in surki mortar	C ft.	6,201		
4	Surki plastering	Sq.	39·00		
5	New burnt stone slabs	S. ft.	2,223		
6	Wooden plug with iron rod, leather washer including locking arrangements.	No.	15		
7	Repairs to sluices	L. S.			
8	New sluice number stones including cutting figures, painting and fixing.	No.	15		
9	Earthwork, cut opening the bund, refilling, excavating foundation and baling water, etc., complete.	L. S.			
10	Concrete in surki mortar	C. ft.	429		
11	Cutting orifices in slabs	No.	26		
12	Cutting holes in guide slabs	„	26		
	OORUKALVE.				
	Channel Works.				
1	Earthwork gravel and stony soil and forming channel bank ...	C. yd.	11,563		
2	Bemoving, painting and refixing existing zero and mile stones ...	No.	4		
3	New furlong stones including cutting figures, painting and fixing ..	„	4		
4	New bank grade stones including cutting figures, painting and fixing...	„	28		
5	New Index stones including cutting figures, painting and fixing ...	„	33		
6	Cutting figures, painting and refixing existing index stones ...	„	24		
7	Cutting figures, painting and refixing existing furlong stones ...	„	21		
8	New bed grade stones including dressing and fixing	„	39		
9	Removing and refixing availrble bed grade stones to the required level.	„	18		
	Head Sluice.				
1	Excavating in soft rock for foundation	L. S.			
2	Surki concrete	C. ft.	89		
3	Burnt brick in surki mortar	„	63		
4	Cement concrete grouting to the joints of flooring and side walls ...	L. S.			
5	New burnt stone slabs	S. ft.	53		
6	Surki plastering	Sq.	2·00		
7	New stone work	C. yd.	5		
8	Old stone work	„	8		
9	Surki concrete grouting with pointing	Sq.	0·60		
10	Repairing pin shutters with new planks whichever necessary ...	L. S.			

No.	Items of work	Per	Quantity	Rate			Cost
				Rs.	a.	p.	Rs.
	Lifting Dam.						
1	Excavation in soft rock for foundation	L. S.					
2	Surki concrete	C. ft.	63				
3	Burnt brick in surki mortar	"	266				
4	New burnt stone slabs	S. ft.	32				
5	New stone work	C. yd.	20				
6	Old stone work	"	3				
7	Fixing old slabs	S. ft.	10				
8	Dismantling masonry, removing plank, baling water, etc.	L. S.					
	Cart Bridges.						
1	Earthwork in gravel and stony soil and forming bank	C. yd.	97				
2	Surki concrete	C. ft.	169				
3	Burnt brick in surki mortar	"	958				
4	Burnt stone slabs, new	S ft.	228				
5	Surki plastering	Sq.	11·52				
6	New stone work	C. yd.	53				
7	Old stone work	"	9				
8	Surki concrete grouting with pointing	Sq.	5·35				
9	Fixing old slabs	S. ft.	120				
10	Dismantling masonry, baling water, etc.	L. S.					
11	New guard stones	No.	16				
12	Dry stone wall work	C. ft.	25				
13	Surki pointing	Sq.	6·25				
14	Repairs to floor	L. S.					
	Relieving Weir.						
1	Earthwork in gravel and stony soil and forming bank	C. yd.	28				
2	Burnt brick in surki mortar	C. ft.	90				
3	New stone work	C. yd.	47				
4	Old stone work	"	28				
5	Fixing old slabs	S. ft.	108				
6	Dismantling masonry	L. S.					
7	Providing new scouring sluice in the existing body wall of relieving weir.	"					
	Masonry Profile.						
1	Earthwork in gravel and stony soil and forming bank	C. yd.	64				
2	Burnt brick in surki mortar	C. ft.	108				
3	New burnt stone slabs	S. ft.	56				
4	New stone work	C. yd.	48				
5	Baling water, etc.	L. S.					
	Improving and reconstructing Sluices.						
1	Earthwork in gravel and stony soil and forming bank	C. yd.	60				
2	Surki concrete	C. ft.	625				
3	Earthwork, cut opening bund, refilling, baling water, etc. ...	L. S.					
4	Burnt brick in surki mortar	C. ft.	6,692				
5	New burnt stone slabs	S. ft.	2,517				
6	Surki plastering	Sq.	41·34				
7	New stone work	C. yd.	278				
8	Wooden plug with iron rod, leather washer and with locking arrangement.	No.	16				
9	Cutting hole in guide slabs	"	26				
10	Cutting orifices in slabs	"	26				
11	Burnt stone slabs 9" thick, dressed...	S. ft.	9				
12	Cutting grooves in slabs for shutters	L. S.					
13	Teakwood shutter with iron bracings complete including locking arrangements.	"					
14	Repairs to sluices						
15	Sluice number stone including fixing	No.	17				

S. A. RAMASWAMY IYER,
Executive Engineer.

HASSAN DIVISION.

Abstract Notification.

The attention of the public is invited to the Notification dated 4th November 1918, published in page 1004 of Part IV of the *Mysore Gazette*, wherein tenders for repairing the Jain Basti temple at Halebid, Belur Taluk, are called for.

Dated 18th November 1918.

Owing to the unsatisfactory seasonal conditions in the State, the public and others who are in need of work are hereby informed that the following works are in progress in this Division.

Persons who are in need of employment, may approach the Sub-Divisional Officers concerned at the places noted against each.